

## Listing of Positive or Assumed Positive Materials with Remaining Quantity Greater than Zero

Site ID California State University, Fullerton

Building ID 9 Langsdorf Hall

<b>Suspect Material/Category</b>	<b>Material Location</b>	<b>Asbestos Present</b>
12"x12" Gray floor tile with white streaks and adhesive	Throughout rooms and hallways Floors 3, 4	Yes
Drywall joint compound	Walls in rooms and hallways Floors 1, 2, 3, 4, 5, 6, 7, 8, & 9	Yes
12"x12" Brown Ceiling Tile	Rooms 206 and 208	Yes (assumed)
Roof Patching Compound	Roof	Yes
Multi-colored sheet vinyl flooring	Adjacent to the elevator Floor: 3	Yes
Red carpet and adhesive with floor tiles underneath	Dean's office Floor: 7	Yes (assumed)
Purple carpet and adhesive with purple floor tile underneath	Receptionist area and offices Floor: 9	Yes (assumed)
12"x12" green floor tile with white streaks	Rooms and hallways Floors: 2, 5, 6, 7, & 9	Yes
4" Baseboard & adhesive	Throughout Floors: 1-9	Yes (assumed)
Blue carpet & adhesive with floor tiles underneath	Throughout Floors: 2, 6, 7, & 8	Yes (assumed)
Gray multi-colored patterned carpet & adhesive over floor tiles	Throughout Floors: 3 & 4	Yes (assumed)